

# NOTES

1. FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES, SEE DWG. E-1. FOR INSTALLATION DETAILS, SEE DWGS. E-2 AND E-4. FOR WIRING DIAGRAMS, SEE DWGS. E-3 AND E-4.
2. CONTRACTOR SHALL REMOVE EXISTING SMOKE DETECTORS ONLY AFTER INSTALLED DEVICES ARE OPERATIONAL.
3. FOR REMOVAL AND PATCHING PLAN DETAILS (P-1, P-2, P-3 & P-4), SEE DWG A-1.
4. FOR RETURN AIR SMOKE DETECTORS ARRANGEMENT AND NOTES, SEE DWG M-1.
5. NOT USED.
6. DISCONNECT AND ABANDON EXISTING SMOKE DETECTOR CIRCUITS IN CEILING. TAPE ENDS OF ABANDONED CONDUCTORS AND TAG AS ABANDONED. THIS WORK SHALL BE DONE IN THE PRESENCE OF THE ENGINEER.

Sheet 29 of 84

THE PORT AUTHORITY  
OF NY & NJ

ENGINEERING PROGRAM MANAGER  
WORLD TRADE  
CENTER  
CHIEF ELECTRICAL ENGINEER

No. Date Revision Approved

ENGINEERING DEPARTMENT

WORLD  
TRADE  
CENTER

ELECTRICAL

Title  
FIRE ALARM SYSTEM  
DEVICE UPGRADE  
PHASE III  
5 WTC 3rd, 4th, 5th & 6th FLOORS

4th FLOOR  
SMOKE DETECTOR  
LAYOUT, INSTALLATION  
AND REMOVAL  
WEST PART PLAN

This drawing subject to conditions in Contract. All inventions, ideas, designs and methods herein are reserved to Port Authority and may not be used without its written consent.

FELDSTEIN APOSTLE A.S.  
Designed by Drawn by Checked by


NOVEMBER 26, 1999  
Date

WTC-861.573 E-04-3W  
Contract Number Drawing Number

I HEREBY CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF ONE OF THE CONTRACT DRAWINGS CONSTITUTING A PART OF CONTRACT NO. WTC-861.573 IN THE FORM IN WHICH SAID DRAWINGS EXISTED AT THE TIME THE SAID CONTRACT WAS EXECUTED BY THE PARTIES.

DATE 2/1/00 F.A. C. M. J.  
CONTRACT ENGINEER/ARCH.

DATE 2/1/00 F.A. C. M. J.  
ENGINEERING PROGRAM MGR.



KEY PLAN  
N.T.S.

0 12 24  
SCALE IN FEET